





Product Approval

USER: Public User

#'s 2,3,8

[Product Approval Menu](#) > **Application Detail**

OFFICE OF THE SECRETARY	FL #	FL46525	
	Application Type	New	
	Code Version	2023	
	Application Status	Approved	
		*Approved by DBPR. Approvals by DBPR shall be reviewed and ratified by the POC and/or the Commission if necessary.	
	Comments		
	Archived	☐	
	Product Manufacturer	Custom Window Systems Inc.	
	Address/Phone/Email	1900 SW 44th Avenue Ocala, FL 34474 (352) 368-6922 certifications@cws.cc	
	Authorized Signature	Mary Rukashaza-Mukome certifications@cws.cc	
	Technical Representative		
	Address/Phone/Email	Mary Rukashaza-Mukome 1900 SW 44th Avenue Ocala, FL 34474 (641) 621-3317 rukashazamc@pella.com	
	Quality Assurance Representative		
	Address/Phone/Email	Steven Bailey 8501 NW 90th St. Medley, FL 33166 (305) 696-8660 sbailey@cws.cc	
	Category	Windows	
	Subcategory	Horizontal Slider	
	Compliance Method	Certification Mark or Listing	
	Certification Agency	Miami-Dade BCCO - CER	
	Validated By	Miami-Dade BCCO - VAL	
	Referenced Standard and Year (of Standard)	Standard TAS 201 TAS 202 TAS 203	Year 1994 1994 1994
	Equivalence of Product Standards		
	Certified By		

Product Approval Method

Method 1 Option A

Date Submitted

02/14/2024

Date Validated

02/26/2024

Date Pending FBC Approval

Date Approved

02/29/2024

Summary of Products		
FL #	Model, Number or Name	Description
46525.1	320 Non-Impact Fin Frame Horizontal Rolling Window	320 Non-Impact Fin Frame Horizontal Rolling Window - XO, OX, XOX Configurations
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +73.3/-100 Other: Please refer to the NOA for all other limitations.		Certification Agency Certificate FL46525_R0_C_CAC_240116_17 - 320 Alum HS.pdf Quality Assurance Contract Expiration Date 02/23/2026 Installation Instructions FL46525_R0_II_240116_17 - 320 Alum HS.pdf Verified By: Thomas J. Sotos, P.E. 55225 Created by Independent Third Party: No Evaluation Reports Created by Independent Third Party:
46525.2	320 Non-Impact Flange Frame Horizontal Rolling Window	320 Non-Impact Flange Frame Horizontal Rolling Window - XO, OX, XOX Configurations
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: No Design Pressure: +73.3/-100 Other: Please refer to the NOA for all other limitations		Certification Agency Certificate FL46525_R0_C_CAC_240116_16 - 320 Alum HS Fl.pdf Quality Assurance Contract Expiration Date 01/26/2026 Installation Instructions FL46525_R0_II_240116_16 - 320 Alum HS Fl.pdf Verified By: Thomas J. Sotos, P.E. 55225 Created by Independent Third Party: No Evaluation Reports Created by Independent Third Party:
46525.3	7200 Impact Fin Frame Horizontal Rolling Window	7200 Impact Fin Frame Horizontal Rolling Window - XO, OX Configurations
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: Yes Design Pressure: +60/-60 Other: Please refer to the NOA for all other limitations.		Certification Agency Certificate FL46525_R0_C_CAC_240116_08 - 7200 Alum HS Fin.pdf Quality Assurance Contract Expiration Date 10/09/2028 Installation Instructions FL46525_R0_II_240116_08 - 7200 Alum HS Fin.pdf Verified By: Thomas J. Sotos, P.E. 55225 Created by Independent Third Party: No Evaluation Reports Created by Independent Third Party:
46525.4	7200 Impact Flange Frame Horizontal Rolling Window	7200 Impact Flange Frame Horizontal Rolling Window - XO, OX, XOX equal lite, XOX un-equal lite Configurations
Limits of Use Approved for use in HVHZ: Yes Approved for use outside HVHZ: Yes Impact Resistant: Yes Design Pressure: +80/-80 Other: Please refer to the NOA for all other limitations.		Certification Agency Certificate FL46525_R0_C_CAC_240116_07 - 7200 Alum HS Fl.pdf Quality Assurance Contract Expiration Date 04/11/2027 Installation Instructions FL46525_R0_II_240116_07 - 7200 Alum HS Fl.pdf Verified By: Thomas J. Sotos, P.E. 55225 Created by Independent Third Party: No Evaluation Reports Created by Independent Third Party:



[Contact Us](#) :: [2601 Blair Stone Road, Tallahassee FL 32399](#) Phone: [850-487-1824](#)

The State of Florida is an AA/EEO employer. [Copyright 2007-2013 State of Florida.](#) :: [Privacy Statement](#) :: [Accessibility Statement](#) :: [Refund Statement](#)

Under Florida law, email addresses are public records. If you do not want your e-mail address released in response to a public-records request, do not send electronic mail to this entity. Instead, contact the office by phone or by traditional mail. If you have any questions, please contact 850.487.1395. *Pursuant to Section 455.275(1), Florida Statutes, effective October 1, 2012, licensees licensed under Chapter 455, F.S. must provide the Department with an email address if they have one. The emails provided may be used for official communication with the licensee. However email addresses are public record. If you do not wish to supply a personal address, please provide the Department with an email address which can be made available to the public. To determine if you are a licensee under Chapter 455, F.S., please click [here](#).

Product Approval Accepts:





DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)
BOARD AND CODE ADMINISTRATION DIVISION

NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY
PRODUCT CONTROL SECTION
11805 SW 26 Street, Room 208
Miami, Florida 33175-2474
T (786) 315-2590 F (786) 315-2599
www.miamidade.gov/building

Custom Window Systems, Inc.
1900 SW 44th Avenue
Ocala, FL 34474

SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami-Dade County) and/ or the AHJ (in areas other than Miami-Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

DESCRIPTION: Series "7200 (Flange Frame)" Aluminum Horizontal Sliding Window – L.M.I.

APPROVAL DOCUMENT: Drawing No. CWS-1220, titled "7200 Aluminum Horizontal Slider Flange Frame Impact Window", sheets 1 through 10 of 10, dated 12/18/23, prepared by manufacturer, and signed and sealed by Thomas J. Sotos, P.E., on 12/18/23 bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and the expiration date by the Miami-Dade County Product Control Section.

MISSILE IMPACT RATING: Large and Small Missile Impact Resistant

LABELING: Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

RENEWAL of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

TERMINATION of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/ or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

ADVERTISEMENT: The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

INSPECTION: A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises NOA #23-1010.04 and consists of this page 1 and evidence pages E-1, E-2, E-3, E-4, E-5, E-6 and E-7, as well as approval document mentioned above.

The submitted documentation was reviewed by Helmy A. Makar, P.E., M.S.



Helmy A. Makar
02/01/2024

NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024
Page 1

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED


1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's

A. DRAWINGS

1. Manufacturer's die drawings and sections.
(Submitted under NOA No. 02-0227.05)
2. Drawing No. **L8700-0901**, titled "HS-8700 Horizontal Rolling Flange Impact Window", sheets 1 through 10 of 10, dated 05/30/09, with revision **H** dated 06/24/22, prepared by manufacturer, signed and sealed by Thomas J. Sotos, P.E.
(Submitted under NOA No. 22-0719.02)

B. TESTS

1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of 3 specimens of a series 8700 impact horizontal rollers, XO configuration, prepared by QAI Laboratories, Test Report No. **QAI-13097**, dated 06/20/22, signed and sealed by Idalmis Ortega, P.E.
(Submitted under NOA No. 22-0719.02)
2. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94
along with marked-up drawings and installation diagram of 3 specimens of an aluminum horizontal sliding window, XO configuration, prepared by National Certified Testing Laboratories, Test Report No. **NCTL-210-4148-01**, dated 06/04/21, signed and sealed by Douglas J. McDougall, P.E.
(Submitted under NOA No. 22-0118.01)
3. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94
along with marked-up drawings and installation diagram of a series HS-8700 flange frame aluminum horizontal sliding window, XO and XOX configurations, prepared by Fenestration Testing Laboratory, Inc., Test Report No. **FTL-10715**, dated 05/08/19, signed and sealed by Idalmis Ortega, P.E.
(Submitted under NOA No. 19-0708.09)




Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

B. TESTS (CONTINUED)

4. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
3) Water Resistance Test, per FBC, TAS 202-94
4) Forced Entry Test, per FBC 2411.3.2.1, and TAS 202-94
along with marked-up drawings and installation diagram of an aluminum horizontal sliding window, XOX (1/4-1/2-1/4 and 1/3-1/3-1/3) configuration, prepared by Hurricane Engineering & Testing, Inc., Test Reports No. **HETI-10-3049** and **HETI-10-3051**, dated 03/23/11, signed and sealed by Candido F. Font, P.E.
(Submitted under NOA No. 11-0705.10)
5. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
along with marked-up drawings and installation diagram of 8 specimens of an aluminum horizontal sliding window, XOX (1/4-1/2-1/4 and 1/3-1/3-1/3) configuration, prepared by Hurricane Engineering & Testing, Inc., Test Reports No. **HETI-10-3047**, **HETI-10-3053**, **HETI-10-3057**, **HETI-10-3130**, **HETI-10-3223** and **HETI-10-3225**, all dated 03/23/11, and signed and sealed by Candido F. Font, P.E.
(Submitted under NOA No. 11-0705.10)
6. Test reports on: 1) Large Missile Impact Test per FBC, TAS 201-94
2) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of an aluminum horizontal sliding window, XOX (1/4-1/2-1/4 and 1/3-1/3-1/3) configuration, prepared by Hurricane Engineering & Testing, Inc., Test Reports No. **HETI-10-3048**, **HETI-10-3049I**, dated 11/09/10, **HETI-10-3050**, **HETI-10-3052B**, **HETI-10-3056**, **HETI-10-3131**, **HETI-10-3224** and **HETI-10-3226**, all dated 03/23/11, and signed and sealed by Candido F. Font, P.E.
(Submitted under NOA No. 11-0705.10)
7. Test reports on: 1) Large Missile Impact Test per FBC, TAS 201-94
2) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of an aluminum horizontal sliding window, XOX configuration, prepared by Hurricane Engineering & Testing, Inc., Test Report No. **HETI-10-3251**, dated 04/25/11, signed and sealed by Rafael E. Droz-Seda, P.E.
(Submitted under NOA No. 11-0705.10)


Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

B. TESTS (CONTINUED)

8. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94

along with marked-up drawings and installation diagram of 8 specimens of an aluminum horizontal sliding window, XO configuration, prepared by Hurricane Engineering & Testing, Inc., Test Reports No. **HETI-08-2033, HETI-08-2034, HETI-08-2035, HETI-08-2036, HETI-08-2037, HETI-08-2038, HETI-08-2116A** and **HETI-08-2116B**, all dated 02/28/08, and signed and sealed by Candido F. Font, P.E.

(Submitted under NOA No. 09-0706.05)

9. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94
3) Water Resistance Test, per FBC TAS 202-94
4) Large Missile Impact Test per FBC, TAS 201-94
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94
6) Forced Entry Test, per FBC 2411 3.2.1, TAS 202-94

along with marked-up drawings and installation diagram of 8 specimens of an aluminum horizontal sliding window, XO configuration, prepared by Fenestration Testing Laboratory, Inc., Test Reports No. **FTL-3097, FTL-3098** and **FTL-3364**, dated 12/06/01, 12/11/01 and 01/28/02, respectively, all signed and sealed by Luis Antonio Figueredo, P.E.

(Submitted under NOA No. 02-0227.05)

C. CALCULATIONS

1. Anchor verification calculations and structural analysis, complying with FBC 7th Edition (2020), dated 05/28/09, revised on 07/10, 01/25/12 and 01/12/22 and updated on 07/13/22, prepared by manufacturer, signed and sealed by Thomas J. Sotos, P.E.
(Submitted under NOA No. 22-0719.02)
2. Glazing complies with **ASTM E1300-09**

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER).



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **20-0915.22** issued to **Kuraray America, Inc.** for their "**Trosifol® Ultraclear, Clear and Color PVB Glass Interlayers**" dated 11/19/20, expiring on 07/08/24.
2. Notice of Acceptance No. **21-0216.01** issued to **Eastman Chemical Company (MA)** for their "**Saflex PVB Interlayers - Clear and Colored for Glass**" dated 04/29/21, expiring on 05/21/26.
3. Notice of Acceptance No. **20-0622.03** issued to **Eastman Chemical Company (MA)** for their "**Saflex Storm - Saflex and Saflex HP Composite Glass Interlayers with PET Core**" dated 08/06/20, expiring on 12/11/23.

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 7th Edition (2020)**, dated July 12, 2022, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
(Submitted under NOA No. 22-0719.02)
2. Statement letter of no financial interest, dated July 12, 2022, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
(Submitted under NOA No. 22-0719.02)
3. Proposal No. **22-0505** issued by the Product Control Section, dated May 12, 2022, signed by Manuel Perez, P.E.
(Submitted under NOA No. 22-0719.02)
4. Proposal No. **19-1433** issued by the Product Control Section, dated January 15, 2020, signed by Manuel Perez, P.E.
(Submitted under NOA No. 22-0118.01)
5. Proposal No. **18-1697** issued by the Product Control Section, dated January 04, 2019, signed by Manuel Perez, P.E.
(Submitted under NOA No. 19-0708.09)
6. Laboratory compliance letter for Test Reports No. **HETI-10-3047, HETI-10-3048, HETI-10-3049, HETI-10-3049I, HETI-10-3050, HETI-10-3051, HETI-10-3052B, HETI-10-3053, HETI-10-3056, HETI-10-3057, HETI-10-3130, HETI-10-3131, HETI-10-3223, HETI-10-3224, HETI-10-3225 and HETI-10-3226**, all issued by Hurricane Engineering & Testing, Inc., dated 11/09/10, 03/23/11 and 04/25/11, signed and sealed by Candido F. Font, P.E.
(Submitted under NOA No. 11-0705.10)



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

1. EVIDENCE SUBMITTED UNDER PREVIOUS NOA's (CONTINUED)

F. STATEMENTS (CONTINUED)

7. Laboratory compliance letter for Test Report No. **HETI-10-3251**, issued by Hurricane Engineering & Testing, Inc., dated 04/25/11, signed and sealed by Rafael E. Droz-Seda, P.E.
(Submitted under NOA No. 11-0705.10)
8. Laboratory compliance letter for Test Reports No. **HETI-08-2033, HETI-08-2034, HETI-08-2035, HETI-08-2036, HETI-08-2037, HETI-08-2038, HETI-08-2116A** and **HETI-08-2116B**, all issued by Hurricane Engineering & Testing, Inc., dated 01/15/08 through 02/28/08, and signed and sealed by Candido F. Font, P.E.
(Submitted under NOA No. 09-0706.05)
9. Laboratory compliance letter for Test Reports No. **FTL-3097, FTL-3098** and **FTL-3364**, all issued by Fenestration Testing Laboratory, Inc., dated 12/06/01, 12/11/01 and 01/28/02, and signed and sealed by Luis Antonio Figueredo, P.E.
(Submitted under NOA No. 02-0227.05)

G. OTHERS

1. Notice of Acceptance No. **22-0118.01**, issued to Lawson Industries, Inc. for their Series "HS-8700 (Flange Frame)" Aluminum Horizontal Sliding Window – L.M.I., approved on 02/24/22 and expiring on 04/11/27.

2. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. **L8700-0901**, titled "HS-8700 Horizontal Rolling Flange Impact Window", sheets 1 through 10 of 10, dated 05/30/09, with revision **I** dated 09/25/23, prepared by manufacturer, signed and sealed by Thomas J. Sotos, P.E.

B. TESTS

1. Test reports on: 1) Uniform Static Air Pressure Test, Loading per FBC, TAS 202-94
2) Large Missile Impact Test per FBC, TAS 201-94
3) Cyclic Wind Pressure Loading per FBC, TAS 203-94
along with marked-up drawings and installation diagram of a series SH-7700 aluminum single hung window, prepared by Hurricane Engineering & Testing, Inc., Test Report No. **HETI-23-8049**, dated 07/24/23, signed and sealed by Ram N. Tewari, P.E.

C. CALCULATIONS

1. None.



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor

NOA No. 24-0116.07

Expiration Date: 04/11/2027

Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

2. NEW EVIDENCE SUBMITTED (CONTINUED)

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. Notice of Acceptance No. **20-0915.22** issued to **Kuraray America, Inc.** for their “**Trosifol® Ultraclear, Clear and Color PVB Glass Interlayers**” dated 11/19/20, expiring on 07/08/24.
2. Notice of Acceptance No. **21-0216.01** issued to **Eastman Chemical Company (MA)** for their “**Saflex PVB Interlayers - Clear and Colored for Glass**” dated 04/29/21, expiring on 05/21/26.
3. Notice of Acceptance No. **22-1130.05** issued to **Eastman Chemical Company (MA)** for their “**Saflex Storm - Saflex and Saflex HP Composite Glass Interlayers with PET Core**” dated 01/26/23, expiring on 12/11/28.

F. STATEMENTS

1. Statement letter of conformance, complying with **FBC 8th Edition (2023)**, dated October 4, 2023, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
2. Statement letter of no financial interest, dated October 4, 2023, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
3. Proposal No. **23-0461R** issued by the Product Control Section, dated June 13, 2023 and revised on June 16, 2023, signed by Manuel Perez, P.E.

G. OTHERS

1. Notice of Acceptance No. **22-0719.02**, issued to Lawson Industries, Inc. for their Series “**HS-8700 (Flange Frame)**” Aluminum Horizontal Sliding Window – L.M.I., approved on 08/11/22 and expiring on 04/11/27.



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

3. NEW EVIDENCE SUBMITTED

A. DRAWINGS

1. Drawing No. **CWS-1220**, titled “7200 Aluminum Horizontal Slider Flange Frame Impact Window”, sheets 1 through 10 of 10, dated 12/18/23, prepared by manufacturer, and signed and sealed by Thomas J. Sotos, P.E., on 12/18/23.

B. TESTS

1. None.

C. CALCULATIONS

1. None.

D. QUALITY ASSURANCE

1. Miami-Dade Department of Regulatory and Economic Resources (RER)

E. MATERIAL CERTIFICATIONS

1. None.

F. STATEMENTS


1. Statement letter of conformance, complying with **FBC 8th Edition (2023)**, dated 12/18, 2023, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
2. Statement letter of no financial interest, dated December 18, 2023, issued by the manufacturer, signed and sealed by Thomas J. Sotos, P.E.
3. Private Labeling Agreement document in conformance to Product Control guidelines dated 01/11/24, signed by Kevin E. Pine, Vice President.

G. OTHERS


1. Notice of Acceptance No. **23-1010.04**, issued to Lawson Industries, Inc. for their Series “HS-8700 (Flange Frame)” Aluminum Horizontal Sliding Window – L.M.I., approved on 11/02/23 and expiring on 04/11/27.



Helmy A. Makar, P.E., M.S.
Product Control Section Supervisor
NOA No. 24-0116.07
Expiration Date: 04/11/2027
Approval Date: 02/01/2024




- NOTE:
- 1) REFER TO SHEET 2 OF 10 FOR INSTALLATION ANCHOR DETAILS AND NOTES.
 - 2) FOR VERTICAL CROSS-SECTION DETAILS "A, A1, B, & B1" REFER TO SHEET #3
 - 3) FOR HORIZONTAL CROSS-SECTION DETAILS "C, D, D1, & E" REFER TO SHEET #4
 - 4) REFER TO SHEET 6 OF 10 FOR DESIGN LOAD CHARTS AND NOTES.



XOX - Equal Lite (1/3-1/3-1/3)

- NOTES:
- 1) REFER TO SHEET 2 OF 10 FOR INSTALLATION ANCHOR DETAILS AND NOTES.
 - 2) FOR VERTICAL CROSS-SECTION DETAILS "A, A1, B, & B1" REFER TO SHEET #3
 - 3) FOR HORIZONTAL CROSS-SECTION DETAILS "D, & E" REFER TO SHEET #5
 - 4) REFER TO SHEET 8 OF 10 FOR DESIGN LOAD CHARTS AND NOTES.



XOX - Un-Equal Lite (1/4-1/2-1/4)

- NOTES:
- 1) REFER TO SHEET 2 OF 10 FOR INSTALLATION ANCHOR DETAILS AND NOTES.
 - 2) FOR VERTICAL CROSS-SECTION DETAILS "A, A1, B, & B1" REFER TO SHEET #3
 - 3) FOR HORIZONTAL CROSS-SECTION DETAILS "D, & E" REFER TO SHEET #5
 - 4) REFER TO SHEET 7 OF 10 FOR DESIGN LOAD CHARTS AND NOTES.

HORIZONTAL SLIDER WINDOW - IMPACT FLANGE FRAME
APPROVED ELEVATIONS

General Notes:

- 1.) THIS WINDOW SYSTEM IS DESIGNED AND TESTED TO COMPLY WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE (2020-7th Edition & 2023-8th Edition, INCLUDING HIGH VELOCITY HURRICANE ZONE (HVHZ) AND ASTM 1300-09. THIS PRODUCT IS IMPACT RESISTANT. (SHUTTERS NOT REQUIRED)
- 2.) WOOD BUCKS SHALL BE INSTALLED AND ANCHORED SO THAT THE BUILDING RESISTS THE SUPERIMPOSED LOADS IN ACCORDANCE WITH THE REQUIREMENTS OF THE FLORIDA BUILDING CODE & TO BE REVIEWED BY BUILDING OFFICIAL.
- 3.) ANCHORS SHOWN ON SHEET 2 OF 10 ARE AS PER TEST UNITS. ANCHORS ON ALL WINDOW SIZES ARE NOT TO EXCEED THESE MAXIMUM SPACINGS ON CENTER (O.C.), AND AS TABULATED ON SHEETS 6, 7, or 8.
- 4.) ANCHOR CONDITIONS NOT DESCRIBED IN THESE DRAWING'S ARE TO BE ENGINEERED ON A SITE SPECIFIC BASIS, UNDER SEPARATE APPROVAL AND TO BE REVIEWED BY BUILDING OFFICIAL.
- 5.) WINDOWS ARE QUALIFIED FOR USE WITH SINGLE GLAZE LAMINATED GLASS TYPES TABULATED HEREIN (SEE SHEETS #6, 7, or 8), AND FOR USE WITH DOUBLE GLAZE LAMINATED INSULATED GLASS TYPES TABULATED HEREIN (SEE SHEETS #6, 7 or 8).
- 6.) WINDOWS WITH GLASS TYPES "A, C, OR G" INSTALLED ABOVE 30FT. IN THE HVHZ, THE I.G. EXTERIOR LITE SHALL BE TEMPERED.
- 7.) SEE SHEET 4 FOR LOCK DETAILS & OPTIONS.
- 8.) SEE SHEET 9 FOR GLASS TYPES.
- 9.) SEE SHEET 6 FOR DESIGN PRESSURES ON "XO or OX" WINDOWS.
- 10.) SEE SHEET 7 FOR DESIGN PRESSURES ON EQUAL-LITE "XOX" WINDOWS.
- 11.) SEE SHEET 8 FOR DESIGN PRESSURES ON UN-EQUAL LITE "XOX" WINDOWS.
- 12.) FOR OPTIONAL FRAME INSTALLATION DETAILS SEE SHEETS 3, 4, or 9.
- 13.) EXT. & INT. FALSE COLONIAL MUNTINS ARE OPTIONAL & AND ARE APPLIED W/ SILICONE
- 14.) WOOD BUCKS IN CONTACT WITH CONCRETE MUST BE PRESSURE TREATED AND ANCHORED (BY OTHERS), PRIOR TO WINDOW INSTALLATION. (SEE SHEET #3, 4 & 5 FOR DETAILS & NOTES) WOOD BUCKS TO BE ANCHORED IN COMPLIANCE WITH THE FBC CHAPTER 24 SECTION 11.3.3.3.
- 15.) APPROVAL APPLIES TO SINGLE UNITS OR SIDE BY SIDE MULLED UNITS.
- 16.) SEE SHEET # 5 FOR MULLION/METAL ATTACHMENT DETAILS, NOTES & OPTIONS.
- 17.) MULLING HORIZONTAL SLIDING WINDOWS WITH OTHER TYPES OF MIAMI-DADE COUNTY APPROVED WINDOWS USING A MIAMI-DADE COUNTY APPROVED MULLION IN BETWEEN ARE ACCEPTABLE BUT THE LOWER DESIGN PRESSURE FROM THE WINDOWS OR MULLION APPROVAL WILL APPLY TO THE ENTIRE MULLED SYSTEM.


PRODUCT REVISED
as complying with the Florida:
Building Code
Acceptance No 24-0116-07
Expiration Date 04/11/2027
By *[Signature]*
Miami Dade Product Control



1900 SW 44TH AVE.
OCALA, FLORIDA 34474
WWW.CWS.CC

**7200 ALUMINUM
HORIZONTAL SLIDER -
IMPACT FLANGE FRAME**

NO.	DESCRIPTION	BY	DATE



DATE **DEC 18 2023**


THOMAS J. SOTOS, P.E.
FL P.E. LIC. # 55225

SHEET DESCRIPTION:
APPROVED ELEVATIONS,
CONFIGURATIONS AND
GENERAL NOTES

DRAWN BY: N. Erazo	DATE: 12/18/2023
REV. BY: ---	DATE: ---
DWG #: CWS-1220	REV #:
SCALE: ---	SHEET 1 OF 10

SCALE:	SHEET 2 OF 10
--------	------------------

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 24-0116-07
Expiration Date 04/11/2027
By H. G. J. Mohr
Miami Code Product Control

[illegible]

THOMAS J. SOTOS, P.E.
FL P.E. LIC. # 55225


SHEET DESCRIPTION:
CROSS SECTION DETAILS,
FIXED INTERLOCK OPTION AND
FRAME INSTALLATION NOTES

DRAWN BY:	DATE:
N. Erazo	12/18/2023

REV. BY:	DATE:
---	---

DWG #:	REV #:
CWS-1220	

SCALE:	SHEET 4 OF 10
--------	------------------



NOTE:
H.D. MEETING RAIL FOR "XD" or "DX" WINDOWS
WITH GLASS TYPE "I" (+80.0 DP and -92.0 DP)
- SEE SHEET 6 OF 10

WINDOW INSTALLATION NOTES:


1. THE WINDOW FRAME FLANGE TO BE BACK-BEDDED W/ AN EXT. GRADE CAULK THROUGHOUT THE ENTIRE PERIMETER OF FLANGE BY WINDOW INSTALLER (TYP.)
2. THE EXPOSED EXT. PERIMETER OF THE WINDOW FRAME TO BE SEALED W/ AN APPROVED EXTERIOR GRADE CAULK BY OTHERS (TYP.)

* WHEN THE GAP BETWEEN THE WINDOW FRAME AND THE BUCK OR MASONRY IS LESS THAN 1/8". SHIMS ARE NOT REQUIRED.

ANCHORS NOTE:

ANCHORS TO BE #12 SMS OR W/D. SCREWS INTO WOOD, OR 1/4" TAPCONS OR APPROVED CONC. FASTENERS INTO CONC., WITH A MINIMUM OF 1 1/4" PENETRATION INTO WOOD OR CONC. (REFER TO LOAD TABLES FOR QUANTITIES REQUIRED)

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 24-0116-07
Expiration Date 04/11/2027
By Helen A. McLean
Miami-Dade Product Control

[illegible]

THOMAS J. SOTOS, P.E.
FL P.E. LIC. # 55225



SHEET DESCRIPTION:
CROSS SECTION DETAILS,
LOCK OPTIONS AND
FRAME INSTALLATION NOTES

DRAWN BY:	DATE:
N. Erazo	12/18/2023

REV. BY:	DATE:
----------	-------

DWG #:	REV #:
CWS-1220	

SCALE:	SHEET 5 OF 10
--------	------------------



1. BOTH EXTRUDED ALUMINUM AND PLASTIC LIFT HANDLE LOCKS ARE QUALIFIED FOR USE ON ALL WINDOWS.
2. BOTH DIE CAST AND NYLON CAM LOCKS ARE QUALIFIED FOR USE ON ALL WINDOWS.
3. TWO (2) LOCKS ARE REQUIRED PER EACH VENT.

WINDOW INSTALLATION NOTES:

1. THE WINDOW FRAME FLANGE TO BE BACK-BEDDED W/ AN EXT. GRADE CAULK THROUGHOUT THE ENTIRE PERIMETER OF FLANGE BY WINDOW INSTALLER (TYP.)
2. THE EXPOSED EXT. PERIMETER OF THE WINDOW FRAME TO BE SEALED W/ AN APPROVED EXTERIOR GRADE CAULK BY OTHERS (TYP.)

* WHEN THE GAP BETWEEN THE WINDOW FRAME AND THE BUCK OR MASONRY IS LESS THAN 1/8", SHIMS ARE NOT REQUIRED.

ANCHORS NOTE:

ANCHORS TO BE #12 SMS OR WD. SCREWS INTO WOOD, OR
1/4" TAPCONS or APPROVED CONC. FASTENERS INTO CONC.,
WITH A MINIMUM OF 1 1/4" PENETRATION INTO WOOD OR
CONC. (REFER TO LOAD TABLES FOR QUANTITIES REQUIRED)

PRODUCT REVISED
as complying with the Florida
Building Code
Acceptance No. 24-0116.07
Expiration Date 04/11/2027
By: Hely A. M...
Miami Dade Product Control

ITEM #	PART #	REQD.	DESCRIPTION	REMARKS
1	L-7703	1	FRAME HEAD	6063-T6 ALUMINUM
2	L-8701	1	FRAME SILL	6063-T6 ALUMINUM
3	L-7701	1	FRAME FXD. JAMB	6063-T6 ALUMINUM
4	L-7704	1	FRAME FIXED MEETING RAIL	6063-T6 ALUMINUM
5	L-7705	1	VENT MEETING RAIL	6063-T6 ALUMINUM
6	L-7707	1	VENT TOP/BOTTOM RAIL	6063-T6 ALUMINUM
7	L-8703	1	FRAME VENT JAMB	6063-T6 ALUMINUM
8	L-7706	1	VENT JAMB LATCH RAIL	6063-T6 ALUMINUM
9	L-8702	1	FRAME SILL TRACK	6063-T5 ALUMINUM
10	L-8705	1	FRAME SILL RETAINING CLIP	6063-T5 ALUMINUM
11	L-7708P	AS REQ'D.	GLAZING BEAD (3/8')	6063-T5 ALUMINUM
12	FS-006	AS REQ'D.	FRAME ASSEMBLY SCREWS	#8 X 3/4' P.H. PHILLIPS
13	FS-040	AS REQD.	INSTALLATION SCREWS	#14 SMS F.H./PHIL.
14	L-7531	AS REQ'D.	VINYL BULB	1/4' DIA. BULB #3033
15	PWS-003	AS REQ'D.	FIN SEAL WEATHERSTRIP	.187" w x .230" h
16	PWS-005	AS REQ'D.	FIN SEAL WEATHERSTRIP	.187" w x .350" h
17	PWS-009	AS REQ'D.	FIN SEAL WEATHERSTRIP	.187" w x .310" h
18	L-7709	AS REQ'D.	GLAZING BEAD (INSULATED)	6063-T5 ALUMINUM
19	PWS-001	AS REQ'D.	PILE @ GLAZING BEAD	.187" w x .150" h
20	*	*	*	*
21	L-7539	2	VENT EXTRUDED SPRING LATCH	6063-T5 ALUMINUM
22	HC-057-1	2	VENT MOLDED SPRING LATCH	MOLDED NYLON
23	L-7523	1 x LATCH	LATCH SPRING	STAINLESS STEEL
24	*	2	SILL/JAMB JOINT GASKET	1/16" CLOSED CELL FOAM
25	FS-041	2	SILL RAIL ASSEMBLY SCREW	#8 X 2 1/4' P.H./PHIL.
26.1	HC-044-1	2	WEEP FLAP & BAFFLE	*
26.2	HC-	1 X WEEP	OPEN CELL FOAM PAD	1/2" X 1/2" X 2' L.
27	HC-040-1	2	SASH ROLLER & HOUSING	*
28	HC-026-1	1	SCREEN FRAME & MESH	*
29	*	1	ATTACHMENT SCREW @ CLIP	#8 X 5/8" S.D.S.
30	HC-058-1	2	VENT SWEEP LATCH	MOLDED NYLON
31	HC-059-1	2	VENT SWEEP LATCH	DIE CAST METAL
32	L-8830	1 X Anchor	FRAME SILL ANCHOR CLIP	6063-T5 ALUMINUM
33	*	2	LAMINATED GLASS	See Details @ L.H. of sheet 9
40 a	"TrueSeal"	AS REQ'D.	Insulated Glass Swiggle Seal	1/4" air space
40 b	"Quanex"	AS REQ'D.	Insulated Glass SuperSpacer	1/4" air space
40 c	"Quanex"	AS REQ'D.	Insulated Glass Duraseal	1/4" air space
34	*	AS REQ'D.	GLAZING SILICONE	See Details @ L.H. of sheet 9
35	L-8301	1	FRAME SILL	6063-T6 ALUMINUM
36	L-8302	1	FRAME SILL RETAINING CLIP	6063-T5 ALUMINUM
37	L-4205	AS REQ'D.	GLAZING BEAD (7/16')	6063-T5 ALUMINUM
38	SM-5504	AS REQ'D.	JOINT SEALANT	*
39	*	AS REQ'D.	EXT. GRADE PERIMETER CAULK	OSI POLYSEAMSEAL

SILICONE OPTIONS
 DOW CORNING 899
 SCHNEE-MOREHEAD 5731
 TREMCO SPECTRUM 2

LAMINATED GLASS COMPOSITION - TYPE I			
ITEM	GLASS DESCRIPTION	DETAIL	LAMINATE DESCRIPTION
1	3/16" HEAT-STRENGTHENED GLASS		SAFLEX "STORM" by Eastman Chemical co.
2	0.077" PLASTIC INTERLAYER		
3	3/16" HEAT-STRENGTHENED GLASS		

SEE MULLION APPROVALS FOR MULLION TYPE, SIZE AND MAX. DESIGN PRESSURE LIMITATIONS.

NOTE: THE LOWER PRESSURES OF THE WINDOW OR MULL SHALL GOVERN

1/4" MAX. SHIM

INTERIOR

12 S.D.S. X 1 1/4" L. (SEE ELEVATION AT SHEET #2 FOR MAX. FASTENER SPACING)

PERIMETER SEALANT

WINDOW FRAME

EXTERIOR

NOTE:

1. ALL STEEL IN CONTACT WITH ALUM. TO BE PAINTED OR PLATED.

1. ALL STEEL IN CONTACT WITH ALUM. TO BE PAINTED OR PLATED.
2. METAL STRUCTURES:
 - A) STEEL : $F_y = 36$ KSI MIN.
(STEEL 18 GA. MIN. THICK - 0.048")
 - B) ALUMINUM : 6063-T5 MIN.
(ALUM. 0.078" MIN. THICK)

A detailed cross-section diagram of a window assembly. The diagram shows multiple layers of glazing and structural components. Callouts include: 19 (top glazing), 18 (top structural layer), 40A, 40B, 40C (top edge components), 34 (central structural layer), 33 (bottom glazing), and 0.600" (dimension for the bottom glazing layer). The text 'GLAZING DEPTH' is written below the 0.600" dimension. To the right of the diagram, the text reads: '*SILICONE OPTIONS*: DOW CORNING 899, SCHNEE-MOREHEAD 5731, TREMCO SPECTRUM 2'.

(*) WINDOWS WITH GLASS TYPES 'A, C, OR G' INSTALLED ABOVE 30FT.
IN THE HVHZ, THE I.G. EXTERIOR LITE SHALL BE TEMPERED.

INSULATED LAMINATED GLASS COMPOSITION TYPE H			
ITEM	GLASS DESCRIPTION	DETAIL	LAMINATE DESCRIPTION
1	1/8" HEAT-STRENGTHENED GLASS		TROSIFOL PVB by Kuraray America, Inc.
2	0.090" PLASTIC INTERLAYER		
3	1/8" HEAT-STRENGTHENED GLASS		
4	1/4" INSULATED AIR SPACE		
5	1/8" TEMPERED GLASS		

40 a) "TrueSeal" Swiggle Seal
40 b) "Quanex" SuperSpacer w/ Isomelt M
40 c) "Quanex" Duraseal

ALUMINUM MULLION
SEE MULLION APPROVALS FOR
MULLION TYPE, SIZE AND MAX.
DESIGN PRESSURE LIMITATIONS.
(ALUM. 0.078" MIN. THICK)


NOTE:
THE LOWER PRESSURES OF
THE WINDOW OR MULL SHALL
GOVERN

12 X 3/4" S.D.S.
FLAT HEAD, PHILLIPS.
(SEE ELEVATION AT SHEET #2
FOR MAX. FASTENER SPACING AND
DP TABLES FOR QUANTITY)

INTERIOR

The diagram shows a cross-section of a window mullion. A dashed rectangular box represents the mullion's profile. Two vertical lines, representing fasteners, pass through the mullion. One fastener is shown in profile, and the other is shown from the front, with a Phillips head. Arrows point from the text labels to the corresponding parts of the drawing: 'ALUMINUM MULLION' points to the dashed box, 'NOTE:' points to the lower part of the mullion, and the fastener specifications point to the fasteners themselves. The word 'INTERIOR' is written at the bottom right, indicating the side of the window.

(E2) FRAME MULLING DETAIL

[illegible]

DATE _____

THOMAS J. SOTOS, P.E.
FL P.E. LIC. # 55225

SHEET DESCRIPTION:
GLAZING DETAILS,
MULLION DETAILS,
AND BILL OF MATERIALS

DRAWN BY: N. Erazo	DATE: 12/18/2023
---------------------------	-------------------------

REV. BY:	DATE:
----------	-------

DWG #:	REV #:
CWS-1220	

SCALE:	SHEET 9 OF 10
--------	------------------

